

Our ref: AB
12th February 2020

Mr C. Rice
Ilminster Cricket Club
Tony Rice Pavilion
Ilminster
Somerset
TA19

Dear Craig

RE: ILMINSTER CRICKET CLUB

We have pleasure in giving our quotation below to refurbish the existing 30.0m x 7.3m artificial double bay cricket facility at the cricket club.

Briefly the work would be carried out as follows:

- The existing carpets would be removed and left on site unless instructed otherwise
- All timbers will be removed and replaced with new treated timber edging (if required)
- The existing timbers inside the nets (batting & bowling ends) will be removed completely with new macadam laid in the gaps
- We would supply and lay a new ECB approved underlay over the whole area
- Finally, we would supply and lay our ECB approved T10 Tufted carpet over the whole area and secure to the new timber edging
- All existing netting would be removed. Installation of a new 18.25 metre long x 7.3 metre wide x 3.6 metre high 2.5mm thick x 40mm square knotless netting in either black or dark green to be hung to existing steelwork.
- Installation of five 3.65m long x 2m new batting sheets in either green or white
- Installation of new vermin skirts both inside and outside of all netting

Our price for the foregoing works including materials, equipment and all labour would be **£9,942.00** exclusive of VAT. **Please Note** - As this is one of our existing facilities this would be an ECB approved system and all of our warranties would be valid (please find attached warranties)

Please note there will be an additional cost of £750.00 + VAT to remove the old carpet and underlay from site

We hope you find the prices quoted to your approval and look forward to hearing further from you in due course.

If in the meantime you require any further information please do not hesitate to contact us.

Yours sincerely,



Adam Brown
Contracts Manager